

REPUBLIC OF KENYA

MINISTRY OF ICT, INNOVATION AND YOUTH AFFAIRS STATE DEPARTMENT OF ICT & INNOVATION

P. O. BOX 30025-00100 NAIROBI

ADDENDUM FOR

TENDER NO: MOICT/SDICT/ONT/003/2021-2022

TENDER FOR SUPPLY, INSTALLATION AND COMMISSIONING OF NETWORK INFRASTRUCTURE AT EMBU PGH LEVEL V HOSPITAL, EMBU COUNTY

ISSUE DATE: 23RD AUGUST, 2021

TENDER CLOSING DATE: 8TH SEPTEMBER, 2021 AT 10.00 A.M

1.0 INTRODUCTION

The Client (Ministry of ICT, Innovation and Youth Affairs, State Department of Ict & Innovation) organized a Pre-Tender Site Survey on 19th August 2021. The was to give the Bidders an opportunity to familiarize with the ground requirements, understand the Tender drawings and identify the omission, adjustments to be considered to ensure installed solution meets the expectation of the intended work. Having gone through the site survey the following was raised and addressed as below:

2.0 ISSUES AND CLARIFICATIONS

No. ISSUES THAT CAME UP	CLARIFICATION
1. The following service points/blocks were not included in the Tender Document namely; a) Oncology block b) Blood Bank/Transfusion Block c) APDK/Orthopaedical Block d) Oxygen Plant Building e) Biomed-engineering	The Bill of Materials, Price Schedule and network design drawings have been amended to reflect the requirements accordingly as specified in section 3.0, section 4.0 and section 5.0 of this Addendum.
2. There is MCH block located outside the main hospital across the Embu Meru Road. Its currently connected to the main hospital using a wireless (p2p).	The MCH Block will still be connected to the main Hospital using the (P2P) The Bidder should ensure that the MCH Network is integrated into the new Network.
3. There was a mix-up of network drawings in the tender document.	The network design drawings have been amended accordingly as specified in section 5.0 of this Addendum.
4. Specifications for Self-Cooling Cabinet in the tender were not clear.	The Specifications for Self-cooling Cabinet has been amended as per the section 2.1 of this addendum

2.1 SELF-COOLING CABINET WITH A POWER SOLUTION

The bidder shall provide a self-cooling cabinet that will include power system, Main Distribution Frame (MDF), Optical Distribution Frame (ODF), battery, environment monitoring and temperature control modules.

No	Technical Specifications	Compliance (Yes/No)	REFERENCE INFORMATION TO SUPPORT COMPLIANCE (Highlighted in the bid document)
Requir	rements		
1.	The solution shall provide efficient power consumption		
2.	It shall easily be deployed in rugged outdoor environments with a temperature range from 41°C to 53°C including high humidity		
3.	Power to the cabinet shall be switched off from within the cabinet. Proper power socket cables to be supplied with the cabinets. The bidder shall be required to provide a 6- Way Power Distribution board		
4.	It shall meet IP55 protection ratings, allowing for installation in adverse conditions such as close to salt water		

		T	
5.	Its door shall be installed with air conditioner		
6.	It shall support remote monitoring and alarms for		
	easier Operations and Maintenance (O&M)		
7.	It shall monitor environmental and power parameters		
8.	The cabinet shall have at least 48V LED lamps with a protective circuit breaker		
9.	The cabinet shall have an AC Distribution Unit with an input Voltage range of 220VAC-240VAC		
10.	The cabinet shall have DC Distribution Unit with an output voltage range between 42-58VDC		
11.	The cooling system shall consist of air conditioners with a cooling capacity of at least 800W, forced air exhaust, heat exchanger and thermoelectric conditioner		
12.	It shall have automatic microclimate control system, security and fire alarms which can engage locally or remote control		
13.	It shall have advanced heat dissipation system to reduce power consumption and noise		
14.	The cabinet should be made of Galvanized steel		
15.	It shall have a fire extinguisher system		
16.	The cabinet shall be at least 38U 19 " mounting racks, which can install 4pcs lead-acid batteries and telecommunication equipment		
17.	The cabinet shall have four 100AH each with 12VDC Lead-acid battery		
18.			
	sensor, water sensor, smoke sensor among others		
19.	The cable inlets should be at the bottom of the cabinet		
20.	Doors should be equipped with a locking system		
21.	It should have a 2year Warranty		

3.0 PRICE SCHEDULE

Bill of Quantities/Schedule of RatesBelow is the amended proposed bill of quantities for guidance.

1. Embu Hospital

	Description	Unit of	Qty	Unit	Total
		Measure		Cost	Cost
1.	F/UTP Category 6A Outlets Module (Data points)	No	738		
2.	Flash Mount Faceplates – F/UTP Category 6A Double	No	369		
3.	F/UTP Category 6A Wall UTP-RJ45Patch cord (1M)	No	782		
4.	F/UTP Category 6A Wall UTP-RJ45Patch cord (3M)	No	738		
5.	F/UTP Category 6A Wall UTP-RJ45Patch cord (5M)	No	10		
6.	F/UTP Category 6A 24 PATCH PANEL 1 U568A/B	No	33		
7.	Cable managers 2U	No	33		
8.	Galvanized Metallic Trunking 150mm x50mm & accessories	Lot	Lot		
	for installing 738 Data Points and access points				

10. Fiber Patch Panel (at least 8 core) No 25	9.	F/UTP Category 6A Pure Copper Ethernet Cable for installing	Lot	Lot	
11. 48 core OFC Patch Panel No 4 12. Fiber Cable 8 Core plus Ducts to interlink all the cabinets/witches No 52 13. Fiber Patch Cord 1M No 52 14. 1G SFP transceivers No 52 15. 18U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU) No 25 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) No 25 17. Rack mountable UPS- 1.5 KVA No 0 0 18. Rack mountable UPS- 3 KVA No 0 0 0 19. Distribution/Aggregation Switch No 1 0 0 20. 48 Port POE+ Switch with Stacking Modules No 8 0 0 21. 24 Port POE+ Switch with Stacking Modules No 17 0 0 22. Wireless Access Point No 44 0 0 0 23. Wireless Controller No 1 0 0 0 0 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 1 1 1 1 0 0 0 25. Installation of Active Devices, IP Schemes and Configuration. Lot Lot Lot 1 1 0 0 0 0 0 0 0 0	10	738 Data Points and access points	NY	25	
12. Fiber Cable 8 Core plus Ducts to interlink all the cabinets/switches 13. Fiber Patch Cord IM 14. IG SFP transceivers 15. I8U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU) 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA 18. Rack mountable UPS- 3 KVA 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules 21. 24 Port POE+ Switch with Stacking Modules 22. Wireless Access Point 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 20. Separation Since Interlink all the cabinetic interlink all the cabinetic size of the cabinetic subject to the cabinetic subject subject to the cabinetic subject					
cabinets/switches 13. Fiber Patch Cord IM No 52 14. 1G SFP transceivers No 52 15. 18U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU) 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA No 25 18. Rack mountable UPS- 3 KVA No 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 21. 24 Port POE+ Switch with Stacking Modules No 22. Wireless Access Point No 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. Lot 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 20. 25 No 21. 24 Port POE+ Switch with Stacking Modules No 1			No	4	
14. 1G SFP transceivers 15. 18U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU) 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA 18. Rack mountable UPS- 3 KVA 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules 21. 24 Port POE+ Switch with Stacking Modules 22. Wireless Access Point 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2	12.		lot	Lot	
15. 18U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU) 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA No 18. Rack mountable UPS- 3 KVA No 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 21. 24 Port POE+ Switch with Stacking Modules No 22. Wireless Access Point No 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 25. No 1	13.	Fiber Patch Cord 1M	No	52	
Distribution Unit (PDU) 16. 38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA No 25 18. Rack mountable UPS- 3 KVA No 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 21. 24 Port POE+ Switch with Stacking Modules No 22. Wireless Access Point No 44 23. Wireless Controller Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 10. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 10. Lot 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2 10. No 2 11. Annual SLA Support for one Year No 2 12. No 2 13. Fiber Optic Pig tail -10M No 2 14. No 2 15. No 2 16. No 2 17. No 2 18. No 2 18. No 19. No 2 10. No	14.	1G SFP transceivers	No	52	
Horizontal Mount Power Distribution Unit (PDU) 17. Rack mountable UPS- 1.5 KVA No 25 18. Rack mountable UPS- 3 KVA No 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 17 22. Wireless Access Point No 14 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. Lot 16 17 18 19 10 10 11 11 12 10 10 11 11 12 11 12 12	15.		No	25	
18. Rack mountable UPS- 3 KVA 19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 21. 24 Port POE+ Switch with Stacking Modules No 22. Wireless Access Point No 44 23. Wireless Controller Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. Lot Lot 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2 SFB – Single mode	16.		No	1	
19. Distribution/Aggregation Switch 20. 48 Port POE+ Switch with Stacking Modules No 8 21. 24 Port POE+ Switch with Stacking Modules No 17 22. Wireless Access Point No 44 23. Wireless Controller No 1 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. Lot Lot 26. Testing, Training and Handover Lot Lot 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2 30. Fiber Optic Pig tail -10M No 2	17.	Rack mountable UPS- 1.5 KVA	No	25	
20. 48 Port POE+ Switch with Stacking Modules 21. 24 Port POE+ Switch with Stacking Modules 22. Wireless Access Point 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2 No 20. No 2 No 2 No 20. Fiber Optic Pig tail -10M	18.	Rack mountable UPS- 3 KVA	No	0	
21. 24 Port POE+ Switch with Stacking Modules No 17 22. Wireless Access Point No 44 23. Wireless Controller No 1 Lot 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. Lot 26. Testing, Training and Handover Lot 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 2 30. Fiber Optic Pig tail -10M No 2	19.	Distribution/Aggregation Switch	No	1	
22. Wireless Access Point 23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No No No No No No No No No N	20.	48 Port POE+ Switch with Stacking Modules	No	8	
23. Wireless Controller 24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode 30. Fiber Optic Pig tail -10M No 2 No 1 Lot Lot Lot Lot 27. Provision of Project Implementation Committee transport as services as specified in Section V no 17 No 2 30. Fiber Optic Pig tail -10M	21.	24 Port POE+ Switch with Stacking Modules	No	17	
24. Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode 30. Fiber Optic Pig tail -10M No 2 Lot Lot Lot Lot No 2 30.	22.	Wireless Access Point	No	44	
and Testing of Horizontal and Backbone Cabling, 25. Installation of Active Devices, IP Schemes and Configuration. 26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode No 20 No 21 No 22	23.	Wireless Controller	No	1	
26. Testing, Training and Handover 27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode 30. Fiber Optic Pig tail -10M No 20 Lot Lot Round Trip 5 21 22 33 No 24 No 25 26 No 26 27 No 28 No 29 20 20 20 20 20 20 20 20 20	24.		Lot	Lot	
27. Provision of Project Implementation Committee transport services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode 30. Fiber Optic Pig tail -10M No Round Trip Year 1 No 2	25.	Installation of Active Devices, IP Schemes and Configuration.	Lot	Lot	
services as specified in Section V no 17 28. Annual SLA Support for one Year 29. SFP – single mode 30. Fiber Optic Pig tail -10M No 2	26.	Testing, Training and Handover	Lot	Lot	
29. SFP – single mode No 2 30. Fiber Optic Pig tail -10M No 2	27.	7 - 7	Round Trip	5	
30. Fiber Optic Pig tail -10M No 2	28.	Annual SLA Support for one Year	Year	1	
	29.	SFP – single mode	No	2	
TOTAL	30.	Fiber Optic Pig tail -10M	No	2	
		TOTAL			

Name of Tenderer:		
	Date	
Authorized Signature of Tenderer:		

4.0 BILL OF MATERIALS

NOTE: The bill of materials is just an estimate; the bidder is required to carry out a survey in order to get actual material required and provision for them in the quote. The client is not liable for any omission.

The Bill of Materials:

1. Embu Hospital

	Description	Unit of	Qty
		Measure	
1.	F/UTP Category 6A Outlets Module (Data points)	No	738
2.	Flash Mount Faceplates – F/UTP Category 6A Double	No	369
3.	F/UTP Category 6A Wall UTP-RJ45Patch cord (1M)	No	782


4.	F/UTP Category 6A Wall UTP-RJ45Patch cord (3M)	No	738
5.	F/UTP Category 6A Wall UTP-RJ45Patch cord (5M)	No	10
6.	F/UTP Category 6A 24 PATCH PANEL 1 U568A/B	No	33
7.	Cable managers 2U	No	33
8.	Galvanized Metallic Trunking 150mm x50mm & accessories for installing 738 Data Points and access points	Lot	Lot
9.	F/UTP Category 6A Pure Copper Ethernet Cable for installing 738 Data Points and access points	Lot	Lot
10.	Fiber Patch Panel (at least 8 core)	No	25
11.	48 core OFC Patch Panel	No	4
12.	Fiber Cable 8 Core plus Ducts to interlink all the cabinets/switches	lot	Lot
13.	Fiber Patch Cord 1M	No	52
14.	1G SFP transceivers	No	52
15.	18U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU)	No	25
16.	38U Self-Cooling, maintenance free Network Cabinet with Horizontal Mount Power Distribution Unit (PDU)	No	1
17.	Rack mountable UPS- 1.5 KVA	No	25
18.	Rack mountable UPS- 3 KVA	No	0
19.	Distribution/Aggregation Switch	No	1
20.	48 Port POE+ Switch with Stacking Modules	No	8
21.	24 Port POE+ Switch with Stacking Modules	No	17
22.	Wireless Access Point	No	44
23.	Wireless Controller	No	1
24.	Civil Works-Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling,	Lot	Lot
25.	Installation of Active Devices, IP Schemes and Configuration.	Lot	Lot
26.	Testing, Training and Handover	Lot	Lot
27.	Provision of Project Implementation Committee transport services as specified in Section V no 17	Round Trip	5
28.	Annual SLA Support for one Year	Year	1
29.	SFP – single mode	No	2
30.	Fiber Optic Pig tail -10M	No	2
	TOTAL		


4 | P a g e

5.0 HOSPITAL BLOCKS WITH PROPOSED NETWORK DATAPOINTS


NOTE: The network drawing and position of datapoints is just proposal the final position will be determined during sign off of network design before implementation. The bidder is required to carry out a survey in order to get actual length and material required and provision for them in the quote. The client is not liable for any omission. The drawings are not to scale.

5.1 Hospital Blocks Overview






Perimeter:22M Doubles: 2 Data Points:4



Perimeter:62M Doubles: 13 Data Points:26

EMBU HOSPITAL PHYSIOTHERAPY AND OCCUPATIONAL THERAPY BLOCK Proposed Network Layout




6m.


Perimeter:131M Doubles: 8

Data Points:16


Perimeter:80M Doubles: 22 Data Points:44



EMBU HOSPITAL NHIF BLOCK Proposed Network Layout




Perimeter:59M Doubles: 12 Data Points:24




Perimeter:24M Doubles: 3 Data Points:6

EMBU HOSPITAL RECORDS BLOCK Proposed Network Layout




Perimeter:48M Doubles: 10 Data Points:20

EMBU HOSPITAL OUTPATIENT BLOCK A Proposed Network Layout




Perimeter:100M Doubles: 18 Data Points: 36

EMBU HOSPITAL OUTPATIENT/CASUALITY BLOCK




Perimeter:122M Doubles: 13 Data Points:26




Perimeter:46M Doubles: 2 Data Points:4

EMBU HOSPITAL MOLECULAR LAB GROUND FLOOR BLOCK Proposed Network Layout



Perimeter:48M Doubles: 2 Data Points:4


EMBU HOSPITAL MOLECULAR LAB 1ST FLOOR BLOCK Proposed Network Layout




Perimeter:42M Doubles: 5 Data Points:10

EMBU HOSPITAL OLD ADMIN BLOCK


Proposed Network Layout




Perimeter:42M Doubles: 5 Data Points:10




Perimeter:70M Doubles: 4 Data Points:8



Perimeter:80M Doubles: 2 Data Points:4




Perimeter:68M Doubles: 3 Data Points:6



Perimeter:136M Doubles:20

Data Points:40




Perimeter:67.8 M

Doubles:8

Data Points: 16

EMBU HOSPITAL X-RAY BLOCK


Proposed Network Layout




Perimeter:4


6.4 M Doubles:1 Data Points:

2




Perimeter:79.4 M Doubles:3 Data Points: 6






EMBU HOSPITAL WARD 1 Proposed Network Layout




1 DOUBLE DATA PLATE 2 DATA POINTS PERIMETER =60.8 M

EMBU HOSPITAL WARD 2 Proposed Network Layout




1 DOUBLE DATA PLATE 2 DATA POINTS PERIMETER =60.8 M

EMBU HOSPITAL WARD 6-7 Proposed Network Layout




3 DOUBLE DATA PLATE 6 DATA POINTS PERIMETER =122.8 M

EMBU HOSPITAL WARD 8-9 Proposed Network Layout




3 DOUBLE DATA PLATE 6 DATA POINTS PERIMETER =122.8 M

EMBU HOSPITAL NUTRITION BLOCK Proposed Network Layout




5 DOUBLE DATA PLATE 10 DATA POINTS PERIMETER =52 M


EMBU HOSPITAL RENAL UNIT Proposed Network Layout



4 DOUBLE DATA PLATE 8 DATA POINTS PERIMETER =61.8 M




2 DOUBLE DATA PLATE 4 DATA POINTS PERIMETER = 64M




2 DOUBLE DATA PLATE 4 DATA POINTS PERIMETER = 77.6M

EMBU HOSPITAL MATERNITY WARD Proposed Network Layout




1 DOUBLE DATA PLATE
2 DATA POINTS
PERIMETER = 65.8M

EMBU HOSPITAL RESOURCE CENTRE Proposed Network Layout




3 DOUBLE DATA PLATE 6 DATA POINTS PERIMETER = 66.6M




1 DOUBLE DATA PLATE 2 DATA POINTS PERIMETER = 100.0M

EMBU HOSPITAL REGISTRY BLOCK Proposed Network Layout



2 OUBLE DATA
PLATE
4 DATA POINTS
PERIMETER = 26.6 M


EMBU HOSPITAL WARD 13—16 BLOCK Proposed Network Layout



Perimeter= 164 Double= 4 Data points=8


50m.

EMBU HOSPITAL NEW ADMIN 2ND FLOOR Proposed Network Layout




Perimeter= 126

Double= 3 Data points=6



Perimeter= 126


Double= 3
Data points=6



Perimeter= 126


Double= 3 Data points=6

EMBU HOSPITAL VCT BLOCK Proposed Network Layout




8 DOUBLE DATA PLATE 16 DATA POINTS PERIMETER =46.5M

EMBU HOSPITAL BIOMETRICAL ENGINEERING GROUND FLOOR Proposed Network Layout



Perimeter= 48.8m Double= 8 Data points=16


EMBU HOSPITAL BIOMETRICAL ENGINEERING 1ST FLOOR Proposed Network Layout




Perimeter= 44.2m Double= 8 Data points=16

EMBU HOSPITAL OXYGEN PLANT 1ST FLOOR Proposed Network Layout


Perimeter= 22.8m Double= 2 Data points=4






EMBU HOSPITAL ORTHOPAEDIC TECHNOLOGY

Proposed Network Layout



Perimeter= 86.1m Double= 9 Data points=18



EMBU HOSPITAL BADEA BLOCK A GROUND FLOOR

Proposed Network Layout

