

ADDENDUM 3

TENDERS FOR SUPPLY, INSTALLATION AND COMMISSIONING OF NETWORK INFRASTRUCTURE UNDER THE UHC PROJECT

The Addendum/Clarifications are as follows:

S/No.	Requirements	Clarifications	Customer Responses
1.	5.6 Aggregate Switch - The proposed switch brand should be rated as Leader or Visionary in Gartner's Magic Quadrant for wired and wireless LAN infrastructure as at the time of tender submission	<p>SECTION V item no. 3p only allows specific vendors listed below to participate in this bid :</p> <ul style="list-style-type: none"> · Cisco, · Juniper, · HPE (Aruba) · Extreme - Huawei <p>Kindly clarify if the tender is restricted to the above vendors or Open to other Vendors/Manufacturers who meet the technical specifications 100%.</p>	This requirement has been dropped for all the active devices
2.	Tender Closing Date was 4 th October, 2022		The Tender Closing date has been extended for a period of seven (No. 7) days so as to close on 11 th October, 2022
3.	BOM for Voi County Referral Hospital		Clarification on the Bill of materials for the Voi County Referral Hospital are as indicated below:

The Bill of Materials for Voi County Referral Hospital

NO.	Description	Unit of Measurement	Qty
1.	F/UTP Category 6A Outlets Module (Data points)	No	400
2.	Flash Mount Faceplates – F/UTP Category 6A Double	No	200
3.	F/UTP Category 6A Wall UTP-RJ45Patch cord (1M)	No	447
4.	F/UTP Category 6A Wall UTP-RJ45Patch cord (3M)	No	400
5.	F/UTP Category 6A Wall UTP-RJ45Patch cord (5M)	No	20
6.	F/UTP Category 6A 24 PATCH PANEL 1 U568A/B	No	20
7.	Cable managers 2U	No	20
8.	Galvanized Metallic Trunking 150mm x50mm & accessories for installing all Data Points and Access Points	Lot	Lot
9.	F/UTP Category 6A Pure Copper Ethernet Cable for installing the required all Data Points and access points	Lot	Lot
10.	Fiber Patch Panel (8-core)	No	15
11.	Fiber Patch Panel (48-core)	No	3
12.	Fiber Patch Panel (24-core)	No	0
13.	Fiber Cable 8 Core plus Ducts to interlink all the cabinets/switches	lot	lot
14.	Fiber Patch Cord 1M	No	31
15.	1G SFP transceivers	No	31
16.	15U Network Cabinet with a 4Way Horizontal Mount Power Distribution Unit (PDU)	No	15
17.	38U Self-Cooling, maintenance free Network Cabinet	No	1
18.	Installation of lightening surge protectors and earthing of the active equipment's	Lot	Lot
19.	Rack mountable UPS- 1.5 KVA	No	15

20.	Decommissioning of Old Cables	Lot	Lot
21.	NOFBI WAN Connectivity Connection and Integration to NOFBI – The hospital is approximately 0.5 Kilometers from nearest NOFBI Node) (2 - Single Mode SFPs, Patch cords, ODF (24 cores), 24 core OFC, Ducts, Hand holes, Manholes)	Lot	Lot
22.	Integration to Existing LANs (Fiber Pigtail, SFP, Flex, etc) where applicable	Lot	Lot
23.	Distribution/Aggregation Switch	No	1
24.	48 Port POE+ Switch with Stacking Modules	No	5
25.	24 Port POE Switch with Stacking Modules	No	10
26.	Wireless Access Point - Indoor	No	42
27.	Wireless Access Point - Outdoor		7
28.	Wireless Controller	No	1
29.	Civil Works-Trenching and manholes; Cable Pulling, Termination, Labelling, Documentation and Testing of Horizontal and Backbone Cabling,	Lot	Lot
30.	Installation of Active Devices, IP Schemes and Configuration.	Lot	Lot
31.	Testing, Training and Handover	Lot	Lot
32.	Certified Training on Routing and Switching on active Devices installed with 6 exam Vouchers	No	6
33.	Provision of Project Implementation Committee transport services as specified in Section V no 17	Round Trip	At least 5 Round Trip
34.	Annual SLA Support for one Year	Year	Year
	TOTAL		